


41000 Main Street Temecula, CA 92590 951-694-6476 TemeculaCA.gov/build permits@TemeculaCA.gov



# Retaining & Block Walls Atop Retaining

#### GENERAL NOTES:

- 1) ALL WORK SHALL CONFORM TO THE ADOPTED CODES AND ZONING REGULATIONS.
- 2) CONCRETE BLOCK MASONRY SHALL COMPLY WITH THE FOLLOWING:
  - A. CONCRETE MASONRY SHALL CONFORM TO ASTM C-90, GRADE N.
  - B. MORTAR: TYPE M OR S.
  - C. GROUT ALL CELLS W/2000 PSI PORTLAND CEMENT GROUT.
- 3) THE ULTIMATE COMPRESSIVE STRENGTH REQUIRED FOR FOUNDATION CONCRETE SHALL BE 2500 PSI.
- 4) ALL REINFORCING STEEL SHALL BE INTERMEDIATE GRADE ASTM A615-40 AND OVERLAP SPLICES SHALL BE 40 BAR DIAMETERS MINIMUM. ALL REBAR HOOKS SHALL BE A MINIMUM OF 12 TIMES THE REBAR DIAMETER (12bd) IN LENGTH.
- 5) PROVIDE RETAINING WALL DRAINAGE SYSTEM AS FOLLOWS: PROVIDE 1CF/FT OF CLEAN COARSE GRAVEL WITH 4" DIAMETER PERFORATED PVC DRAINAGE PIPE WITH 1% GRADIENT TO DRAIN - OR OMIT HEAD JOINTS IN FIRST COURSE.
- 6) OPTIONAL: INSTALLATION OF A MOISTURE BARRIER ON THE FILL SIDE OF THE WALL WILL HELP TO PREVENT MOISTURE FROM PENETRATING THE VISIBLE SIDE OF THE WALL, RESULTING IN DISCOLORATION.
- 7) THIS RETAINING WALL STANDARD IS NOT DESIGNED TO SUPPORT SURCHARGE LOADS FROM MOTOR VEHICLES OR OTHER STRUCTURES.
- 8) CLEANOUTS SHALL BE PROVIDED FOR ALL GROUT POURS OVER 5 FEET IN HEIGHT. WHERE REQUIRED. CLEANOUTS SHALL BE PROVIDED IN THE BOTTOM COURSE AT EVERY VERTICAL BAR AND SHALL BE SEALED AFTER INSPECTION AND BEFORE GROUTING.

#### REQUIRED INSPECTIONS:

1) FOOTING:

EXCAVATION TRENCH CLEAN WITH STEEL IN PLACE AND SUPPORTED 3" ABOVE AND AWAY FROM THE SURROUNDING EARTH/DIRT.

2) REBAR/PRE-GROUT and DRAINAGE SYSTEM;


BOND BEAM REBAR AND VERTICAL REBAR IN PLACE - INSPECTION PRIOR TO PLACING GROUT. DRAINAGE SYSTEM COMPLETE.

3) FINAL:

AFTER GROUT IS PLACED AND BACKFILL COMPLETED - PRIOR TO ANY DECORATIVE CAP PLACEMENT.

## SETBACK FROM TOP OF SLOPE:

All footings adjacent to slopes to be at least 5' to daylight as shown below.



#### DISCLAIMER:

Alternate retaining wall designs may be possible when provided with an engineered analysis. Use of this standard design is at the user's risk and carries no implied or inferred guarantee against failure or defects.

## **DESIGN PARAMETERS:**

ACTIVE SOIL PRESSURE (PSF) LEVEL BACKFILL = 30 SLOPING (2:1 MAX) = 43 PASSIVE SOIL BEARING (PSF) =150 COEFFICIENT OF FRICTION = 0.25ALLOWABLE SOIL BEARING PRESSURE (PSF) =1500 (NO INCREASES TAKEN FOR DEPTH OR WIDTH OF FOOTING)



04/17/2014


951-694-6439

41000 Main Street Temecula, CA 92590

PAGE 2 OF 4




41000 Main Street Temecula, CA 92590 951-694-6476 TemeculaCA.gov/build permits@TemeculaCA.gov




- 3) all rebar to be astm spec. A615, grade 40 minimum.
- 4) all rebar lap splices to be 24" minimum.
- 5) all masonry units to be astm C-90 grade N.
- 6) not designed for surcharge loads from vehicles or structures.

## DISCLAIMER:

Alternate designs may be possible when provided with an engineered analysis. Use of this standard design is at the user's risk and carries no implied or inferred guarantee against failure or defects.



\*SEE PAGE 2 FOR ADDITIONAL INFORMATION\*





41000 Main Street Temecula, CA 92590 951-694-6476 TemeculaCA.gov/build permits@TemeculaCA.gov

